

<b>SOLICITATION/CONTRACT/ORDER FOR COMMERCIAL ITEMS</b> <i>OFFEROR TO COMPLETE BLOCKS 12, 17, 23, 24, &amp; 30</i>				1. REQUISITION NUMBER <b>PR5438872</b>	PAGE 1 OF 1 of 1	
2. CONTRACT NO.	3. AWARD/EFFECTIVE DATE	4. ORDER NUMBER	5. SOLICITATION NUMBER <b>S-JO100-16-Q-0034</b>	6. SOLICITATION ISSUE DATE <b>July 20, 2016</b>		
7. FOR SOLICITATION INFORMATION CALL: 	a. NAME <b>Mahmoud M. Itani</b>		b. TELEPHONE NUMBER(No collect calls) <b>(962) 6 590-6133</b>	8. OFFER DUE DATE/ LOCAL TIME <b>August 04,2016 14:00</b>		
9. ISSUED BY <b>General Services Office American Embassy P.O Box 354  Amman-Jordan Tel: (962) 6 590-6000 Fax: (962) 6 592-7957</b>		CODE	10. THIS ACQUISITION IS <input type="checkbox"/> SMALL BUSINESS <input type="checkbox"/> HUBZONE SMALL BUSINESS <input type="checkbox"/> SERVICE-DISABLED VETERAN-OWNED SMALL BUSINESS <input type="checkbox"/> EDWOSB <input type="checkbox"/> 8 (A) SIZE STANDARD:			<input checked="" type="checkbox"/> UNRESTRICTED OR <input type="checkbox"/> WOMEN-OWNED SMALL BUSINESS <input type="checkbox"/> (WOSB) ELLIGIBLE UNDER THE WOMEN-OWNED SMALL BUSINESS PROGRAM NAICS: <input type="checkbox"/> SET ASIDE: ___ % FOR:
11. DELIVERY FOR FOB DESTINATION UNLESS BLOCK IS MARKED <input type="checkbox"/> SEE SCHEDULE	12. DISCOUNT TERMS		<input type="checkbox"/> 13a. THIS CONTRACT IS A RATED ORDER UNDER DPAS (15 CFR 700)		13b. RATING	
15. DELIVER TO <b>American Embassy Amman-Jordan</b>		CODE	16. ADMINISTERED BY <b>General Services Office American Embassy P.O Box 354</b>			
17a. CONTRACTOR/OFFERER	CODE	FACILITY CODE	18a. PAYMENT WILL BE MADE BY <b>General Services Office American Embassy P.O Box 354</b>			
<input type="checkbox"/> 17b. CHECK IF REMITTANCE IS DIFFERENT AND PUT SUCH ADDRESS IN OFFER			18b. SUBMIT INVOICES TO ADDRESS SHOWN IN BLOCK 18a UNLESS BLOCK BELOW IS CHECKED <input type="checkbox"/> SEE ADDENDUM			
19. ITEM NO.	20. SCHEDULE OF SUPPLIES/SERVICES		21. QUANTITY	22. UNIT	23. UNIT PRICE	
1	<b>EMBASSY COMPOUND ASPHALT RESURFACING AND CURB STONE INSTALLATION AS PER ATTACHED SOW</b> <i>(Use Reverse and/or Attach Additional Sheets as Necessary)</i>		1	service		
25. ACCOUNTING AND APPROPRIATION DATA				26. TOTAL AWARD AMOUNT <i>(For Govt. Use Only)</i>		
<input checked="" type="checkbox"/> 27a. SOLICITATION INCORPORATES BY REFERENCE FAR 52.212-1, 52.212-4. FAR 52.212-3 AND 52.212-5 ARE ATTACHED. ADDENDA			<input checked="" type="checkbox"/> ARE <input type="checkbox"/> ARE NOT ATTACHED			
<input checked="" type="checkbox"/> 27b. CONTRACT/PURCHASE ORDER INCORPORATES BY REFERENCE FAR 52.212-4. FAR 52.212-5 IS ATTACHED. ADDENDA			<input checked="" type="checkbox"/> ARE <input type="checkbox"/> ARE NOT ATTACHED			
<input type="checkbox"/> 28. CONTRACTOR IS REQUIRED TO SIGN THIS DOCUMENT AND RETURN 0 COPIES TO ISSUING OFFICE. CONTRACTOR AGREES TO FURNISH AND DELIVER ALL ITEMS SET FORTH OR OTHERWISE IDENTIFIED ABOVE AND ON ANY ADDITIONAL SHEETS SUBJECT TO THE TERMS AND CONDITIONS SPECIFIED HEREIN.			<input type="checkbox"/> 29. AWARD OF CONTRACT: REF. _____ OFFER DATED _____, YOUR OFFER ON SOLICITATION (BLOCK 5), INCLUDING ANY ADDITIONS OR CHANGES WHICH ARE SET FORTH HEREIN, IS ACCEPTED AS TO ITEMS:			
30a. SIGNATURE OF OFFEROR/CONTRACTOR			31a. UNITED STATES OF AMERICA <i>(SIGNATURE OF CONTRACTING OFFICER)</i>			
30b. NAME AND TITLE OF SIGNER <i>(Type or print)</i>	30c. DATE SIGNED	31b. NAME OF CONTRACTING OFFICER <i>(Type or print)</i>		31c. DATE SIGNED		
		<b>Shayna Michael</b>				



Embassy of the United States of America

Amman, Jordan

FACILITY MANAGEMENT OFFICE

## **SCOPE OF WORK**

**DATE:** June 17, 2016

**PROJECT:** EMBASSY COMPOUND ASPHALT RESURFACING - OVERLAY PROJECT

**LOCATION:** Embassy Compound- U.S. Embassy

### **1. SPECIFICATIONS/SCOPE OF WORK**

Asphalt resurfacing - overlay project located within roadways of U.S. Embassy compound. Project includes approximately 1,010 square meters of existing surfaced roadway or approximately 157 linear meters of roadway.

Curb Stone installation- approximately 118 linear meters of new curb stone to be installed on both sides of the road in some areas.

### **2. Scope of Work:**

The asphalt paving contractor shall furnish all necessary equipment, labor, and material and permits required to install the asphalt overlay (resurfacing) of the existing roads, and other work as indicated including:

- Cleaning loose sand and dirt from the existing paved surface.
- Repairing and filling of existing pot holes and boils. Grind down area and level prior to resurfacing.
- Leveling of low / depressed areas

- . • Application of asphalt bonding materials to create a bond between the existing surface and the new asphalt.
- The asphalt resurfacing full overlay shall consist of installation of Structural Hot Mix Asphalt at a target thickness of 2 inches and an actual distribution of 220 lbs. per square yard averaged over the entire area to be resurfaced. Asphalt must be rolled and compacted to a minimum depth of two inches (5 cm). (Minimum 98% compacted)
- The newly placed asphalt shall tie in smoothly with the existing road surface.
- Existing driveways will be cold planed or cut out and the newly placed 2" overlay shall conform to the smoothness and drainage of existing paved driveways and roadways.
- Apply new surface to improve or correct any existing drainage Issues.
- Maintain integrity of existing gutters drainage culverts or any drainage apparatus.
- Contractor shall install approximately 118 linear meters of curb stone on both sides of part the road as shown in Fig 1.2
- All materials and application methods shall be in conformance with current U.S. Standard Specifications.
- Spoils shall be properly disposed of offsite at no additional charge to the Embassy.
- The work includes mobilization and all necessary traffic control. Contractor shall provide all signage necessary for the project.
- Access to the ambassador's house must be maintained at all times, resurfacing works will be executed in two phases if necessary.
- Daily cleaning the work site of all construction debris, leaving the area safe ready for traffic.
- Work area must be cordoned off at all times unless otherwise instructed by the U.S. embassy project engineer.

### **3. PROJECT SCHEDULE & WORKERS.**

- a. Work days to be coordinated with Facilities Manager( FM)/Contracting Officer's Representative ( COR) , work shall be performed during working hours, after working hours and during weekends.
- b. Duration of the project shall not exceed 7 days from the start date.
- c. Work hours will be from 0800 to 1630, Saturday through Friday.

#### **4. QUALITY CONTROL**

- a. The contractor shall designate a site supervisor to be present at all times on the project site.
- b. Site Supervisor will ensure that standard industry practices as defined in the International Code are applied and followed at all times.
- c. A final inspection will be held with the Embassy, contractor and the Site Supervisor to inspect for quality of the finished works.

#### **5. SAFETY**

- a. Site Supervisor will ensure that all equipment used during the project is in safe operating condition. All personnel on the job site will be given the appropriate safety equipment. The Embassy reserves the right to stop the work if any unsafe conditions are found.
- b. All electrical equipment such as air compressors, buffing machines and any extension cords must be properly grounded and be free from any defect in the insulation

#### **6. SECURITY**

- a. A list of all personnel working on the project along with Identification numbers must be submitted to the embassy no later than 5 working days prior to the beginning of actual starting date of the project.
- . b. While on the Embassy property, all personnel must be escorted at all times. Any personnel found unescorted will be removed from the project immediately.
- c. Job site personnel will be issued a visitors badge by the Security staff, and this badge must be worn at all times.



Fig. 1.1 Existing Conditions 1



Fig 1.2 Existing Conditions 2- Curb stone